



NOTES:

1. The works are to be undertaken in accordance with Highway Agency Manual of Contract Documents for Highway Works (MCDHW).
2. All dimensions are in millimetres unless otherwise shown.
3. All concrete shall be standard mix ST4 unless otherwise stated.
4. Allow for up to 1.5m excavation for all drainage pipework for pricing purposes
5. Allow for the reinstatement of all existing surfaces on completion.
6. All drainage features to be to D400 Carriageway loading.
7. Allow for the repositioning / replacement of all kerbing / edging as required during the works.

- EXISTING DRAINAGE FEATURES
- PROPOSED DRAINAGE FEATURES
- - - RAISE SETTS / PCC KERBS TO 20mm UPSTAND. INCLUDE FOR ADJUSTING DROPPER KERBS TO SUIT
- ▨ ALLOW FOR ALL INVERT OF DITCHES TO BE LOWERED BY MINIMUM 400mm

ALLOW FOR THE REMOVAL OF ALL ACCEPTABLE / UNACCEPTABLE MATERIAL FROM SITE TO LICENSED TIP.
FOR STANDARD DETAILS SEE DRAWING C12DRAIN120/STD/01 rev 0

This map is reproduced from Ordnance Survey material with the permission of the Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. Buckinghamshire County Council 100021529 [2018]

Rev	Rev. Date	Purpose of revision	Drawn	Checked	Approved
1	June 2018	DRAINAGE NETWORK REVISED.	JCR	KB	KB
0	Jan 2018	FOR ISSUE	JCR	KB	KB

Transport for Buckinghamshire
County Hall, Walton Street, Aylesbury, Buckinghamshire, HP20 1UY

Client: **BUCKINGHAMSHIRE COUNTY COUNCIL**
MARK KEMP
DIRECTOR, GROWTH, STRATEGY AND HIGHWAYS
TRANSPORT ECONOMY ENVIRONMENT

Project: **VALLEY ROAD HUGHENDEN VALLEY**

Drawing title: **PLAN TO SHOW PROPOSED DRAINAGE REMEDIAL WORKS**

Drawing status: **FOR ISSUE**
Scale: **1:500 @ A3 (UNLESS STATED) DO NOT SCALE**
Project No.: **C12DRAIN120**

Drawing number	Rev
C12DRAIN120/DRN/01	1

This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing.